

Project:

COMPTON COMMUNITY COLLEGE DISTRICT- FOOTBALL

FIELD

ADDENDUM NO. 1

Date:

June 17, 2015

Owner:

Compton Community College District

1111 E. Artesia BLVD Compton, CA 90221 (310) 900-1600

Architect:

Ghataode Bannon Architects LLP

760 W. 16th Street, unit B Costa Mesa, CA 92627

(714) 665-8030

The clarifications, modifications, changes, additions, and/or deletions contained herein shall be incorporated within the construction documents for the project. Such information shall take precedence over that previously published.

GENERAL

Item No. 1.1

Description:

Add the attached Pre-Bid RFI Responses for the following RFI:

- 1. PB001
- 2. PB002
- 3. PB003
- 4. PB004
- 5. PB005
- 6. PB006
- 7. PB007
- 8. PB008
- 9. PB009
- 10. PB010
- 11. PB011
- 12. PB012
- 13. PB013

Item No. 1.2

Description:

Add the Attached Electrical & Low Voltage Drawings & Specifications

- 1. DRAWINGS:
 - a. E101- Electrical Symbols List
 - b. E101- Electrical Site Plan
 - c. E201- Single Line Diagram and Enlarged Electrical Room

Project: COMPTON COMMUNITY COLLEGE DISTRICT- FOOTBALL FIELD

ADDENDUM NO. 1 Date: June 17, 2015 Page 2 of 2

- d. E301- Electrical Details
- e. E401- Electrical Specifications
- **E402- Electrical Specifications**

Item No. 1.3 Replaced Specifications

Description: Replace the following specification sections with the attached version as

1. Section 11 68 33

2. Section 00 43 50

Item No. 1.4 Rodent Control

Description: Provide rodent control per the following specification:

> A. Pest Control: Engage pest-control service to recommend practices to minimize attraction and harboring of rodents, roaches, and other pests and to perform extermination and control procedures at regular intervals so Project will be free of pests and their residues at Substantial Completion. Perform control operations lawfully, using

environmentally safe materials.

Item No. 1.5 Soils Reports

Description: Soils Report Dated June 8, 2015

Alternative Site Preparation Recommendations Dated June 10, 2015

END OF ADDENDUM NO. 1

PCM3 #_____ (For PCM3 Use Only)

			RFI No.
TO DOME Inc. Do	f No.:		1 - 1 Bid Pkg. RFI No.
TO: PCM3, Inc. Re ckober@pcm3.com	1 140.5		ыа Pkg. RFI No.
FROM: P.H. Hagopian Cor	tractor, Inc.	DWG. REF.: C003	3 Table 1
Fax No: 714-543-5825			
Site CCCD Footba			
		Spec. Ref:	
Bid Pack: 1 Irada not SP No.			6/16/2015
<u>Trade</u> not SP No.		Academ Ach	andread decrea desid desided deside
Description of Problem / Clarification	/Information Required:		
Is Geo Grid alternative per square for	•	er unit?	
23 COO GAIA LINGTHALING POT DALARIO 100	or or order motor or other our	UI UIIII	
Drawings attached -			
,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,			
Proposed Solution:			
•			
Question By: P. H. Hagopian Co.	ntractor, Inc.	Date:	6/16/2015
Fadin Field			
Response: Entire Field			

And an about more and on the street and the street and the street of the			
, , ,	Provide a language and the second		
Response By: Brett	Digitally signed by Brett Houser DN: cn=Brett Houser, o=G8A, LLP,	Date:	
Reviewed By: Houser			
Neviewed by: [1003C]	Date: 2015.06.17 10.55:55 -07'00'	Date:	

PCM3 #______ (For PCM3 Use Only)


				RFI No.
	PCM3, Inc. Ref No kober@pcm3.com	o.;		1 sid Pkg. " 2 RFI No.
	.H. Hagopian Contrac	tor, Inc. DW	G. REF.: <u>C0</u> 0	3 Table 1
Fax No: 7	14-543-5825			
Site <u>C</u>	CCCD Football I	<u>Field</u>		
		Sr	oec. Ref:	
Bid Pack: _	1 Trade not BP No.	·		6/16/2015
Nasadudian of Deale	lana I Chaddiaadhaa I la	f		
-	lem / Clarification / Int	·		
s asphait section o	f 3" intended to be in	two 1 1/2" litts?		
				~~~~~
rawings attached -	,			
	*** **********************************			**************************************
Proposed Solution:				
Toposea Solution.				
Question By: P	. H. Hagopian Contra	ctor, Inc.	Date:	6/16/2015
Response:				
		phalt shall be 1" thick.		
		alt shall be 2" thick.		
Ron Canedy, Fi	PL & Associates			
6-17-2015		provide and the provide		
<del> </del>	Brett	Digitally signed by Brett Houser DN: cn=Brett Houser, o=GBA,		
			e	
Response By: _	Houser -	t, c=US Date: 2015.06.17 10:58:57 -07'00	Date:	
Reviewed By:		Date, 2013/00/17 10/30/37 10/100	Date:	

## PCM3 #______ (For PCM3 Use Only)

		Г	RFI No.
TO:	PCM3, Inc. Ref No.: ckober@pcm3.com		1 - 3 8id Pkg. RFI No.
FROM	: P.H. Hagopian Contractor, Inc.	ــــــ :DWG. REF	
	: 714-543-5825		
	CCCD Football Field		
	<u></u>		
nu n			
BIU PACK	Trade not BP No.	Date:	6/16/2015
Description of Pro	oblem / Clarification / Information Req	uired:	
it was discussed	at the job walk that a laydown area ad	jacent to the stadium on th	e east side would be
required. That the	Contractor would need to blade it of	f, remove grass from area,	dispose of grass and
gravel, and fence	it off. No provisions are shown on the	e drawings. Is the laydown	required?
- The section size with sea in this section size, section is			
***************************************			
Drawings attache			
No. Co. Co. Co. Co. Co. Co. Co. Co. Co. C			
Proposed Solutio	n:		
****			
Question By:	P. H. Hagoplan Contractor, Inc.	Date:	6/16/2015
Response:	Yes a laydown area is required for th	e displaced soil from the fi	eld (soil only) and for
-	delivery and staging area for the KY	A provided materials for the	synthetic turf. This
***************************************	laydown area will remain under secu	<del></del>	
		FFTTTTTTTTTTTTTTTTTTTTTTTTTTTTTTTTTTTT	
B		n	
Kesponse By:		Date:	
Reviewed By:		Date:	

## REQUEST FOR INFORMATION PCM3 #_____ (For PCM3 Use Only)

				RFI No.
то		ł		1 - 4 Bid Pkg. RFI No.
ERON	ckober@pcm3.com	or Inc	DIA/C BEE:	
	A: P.H. Hagopian Contract	or, inc.	DWG. REP.:	
	o: 714-543-5825			
SIL	e <u>CCCD Football F</u>	<u>ieia</u>		
Bid Pac	k: 1 Trade not BP No.	•	Date:	6/16/2015
Description of P	roblem / Clarification / Info	rmation Required:		
It was discussed	I at the job walk that the C	ontractor was to bla	de off areas around	the track to a depth of 3"
first spraying we	ed kill, applying rodent ab	atement measures,	and removing weed	s, then installing Pro Gold
No plan has bee	n included to determine th	e quantity of Pro Go	ld require. Will Pro	Gold be required? If so,
Please furnish p	lan and provide spec on re	odent abatement and	l length of maintana	ance.
Drawings attach	ed -			
Proposed Solution	on:			
***************************************				
-		¥5500 <b>×</b> 55-26	Table And Profession	
Question By	y: P. H. Hagopian Contract	or, Inc.	Date:	6/16/2015
Response:	1. See attached site plan	showing location o	utlined in red.	
	2. Provide per specificat	ion section 01 01 00	Scope of Work 1.2.	A.1.J.
	3. Existing contours to r			
	4. See Addendum No. 1	tem 1.4 for rodent a	batement requireme	ents.
	5. There is no maintenar			
Resnonse By	Brett	Digitally signed by Brett House	' Date:	************************
		_DN: cn=Brett Houser, o=G8A, LLP, ou, email=bhouser@gbarchitects.r		
Reviewed By	"- Houser	t, c=US	Date.	****************
			8	



ARTESIA BOULEVARD Compton CCD Football Field RFC # 4 Pro Gold Area

## REQUEST FOR INFORMATION PCM3 #______(For PCM3 Use Only)

			Γ	RFI No.
TO:	PCM3, Inc. Ref No.: ckober@pcm3.com			1 8id Pkg 5 RFI No.
FROM:	P.H. Hagopian Contract	or, Inc.	DWG. REF.:	
Fax No:	714-543-5825			
Site	CCCD Football F	<u>ield</u>		
			Spec. Ref:	02 21 33 Paragraph 1.6
Bid Pack:	1 Trade not 8P No.		Date:	6/16/2015
Description of Pro	blem / Clarification / Info	nnation Required:		
Are arial photogra	phs of the entire job site	taken prior to the start	of constructio	n, monthly, and at the
conclusion of con	struction required?			
Drawings attached				
	P. H. Hagopian Contract			6/16/2015
	1.6 will not be re	equired for this	project.	02 21 33 Part
Response By:	Brett Houser	Digitally signed by Brett House DN: cn=Brett Houser, o=GBA, El ou,	r LP, Date:	
Reviewed By:	Dictinousei	email=bhouser@gbarchitects.n 		

PCM3 #______ (For PCM3 Use Only)

			[	RF	No.
то:	PCM3, Inc. Ref No ckober@pcm3.com	s.i		<u>1</u> Bid Pkg.	RFI No.
FROM	: P.H. Hagopian Contrac	tor, Inc.	DWG. REF.:		
	: 714-543-5825	<b>-</b>			
	CCCD Football I				
			Cana Dafe	44 60 22	#4 4 42
Did Dack	4			11 68 33	/2015
Diu Fack	Trade not BP No.		wate.		12010
Description of Pr	oblem / Clarification / Inf	formation Required:			
	58 33 number 1.1 A2 requ				
spec section 68	33 61 states the goal pos	t footings are Owner fur	nished and in	stalled. Which	is it?
	**************************************				
	ed -				
Proposed Solution	on:				
Question By	: P. H. Hagoplan Contrac	ctor, Inc.	Date:	6/16	/2015
Response:	We don't have :	section 68 33 6	1 in this	project. (	Goal post
nesponse.	footings shall be			, ,	•
***************************************					
Response By	Brett	Digitally signed by Brett House DN: cn=Brett Houser, o=GBA, LLP, ou,	Date:		
Reviewed By	Houser	email=bhouser@gbarchitects. 	Date.		

#### REQUEST FOR INFORMATION

PCM3 #____ (For PCM3 Use Only)

			RFI No.
TO: PCM3, Inc. Ref No ckober@pcm3.com	o.:		1 - 7 8id Pkg RFI No.
FROM: P.H. Hagopian Contra	ctor, Inc.	OWG. REF.:	
Fax No: 714-543-5825			
Site CCCD Football	<u>Field</u>		
		Spec. Ref:	01 01 00-05
Bld Pack: 1 Trade rot BP No.	a ava av	Date:	6/16/2015
Description of Problem / Clarification / Ir	nformation Required:		
Spec section 01 01 00-05 states that "Co	ntractor will Provide: A Fu	I Time Security	Guard within the
construction area, the lay down area and	d will be coordinated with (	Campus Police	from July 1- August 31,
2015".			
Does this mean that a security guard wil			
Superintendent is not there including we	eekends, holidays, etc?		
Proposed Solution:			
Question By: P. H. Hagopian Contra	actor, Inc.	Date:	6/16/2015
Yes Response:			
***************************************			
Rratt	Digitally signed by Brett Houser		
Response By: Brett	ON: cn=Brett Houser, a=GBA, LLP, ou, email=bhouser@gbarchitects.net,	Date:	
Reviewed By: Houser	c=U5 Date: 2015.06-17.44:01:4707'00'	Date:	

PCM3 #______ (For PCM3 Use Only)

TO:	PCM3, Inc. Ref No	o.:		RFI No.  1 - 8  Bid Pkg. RFI No.
FROM	: P.H. Hagopian Contrac	etor, Inc.	 DWG, REF.:	
	: 714-543-5825		_ *************************************	
	CCCD Football	Field		
Oito	GGGB ( COURT	<u> </u>		
	_			01 01 00-07
BIO Pack	1 Trade not 8P No.		Date:	6/16/2015
•	oblem / Clarification / In consible to remove synt	•	ebris and keep	site clean for synthetic turf
contractor's oper	ations? Is Contractor re	sponsible for any dama	ge done by syn	thetic turf contractor as it
pertains to items	listed in 01 01 00-05 iter	n C		
Drawings attache	d -			
Proposed Solutio				
Question By:	P. H. Hagopian Contra	ctor, Inc.	Date:	6/16/2015
Response: 1	. Yes			
•	. No			
Response By:	Brett	Digitally signed by Brett Ho DN:cn=Brett Houser, o=GB	user	
Reviewed By:	Houser	email=bhouser@gbarchited c=US	cts.net, Date:	

## REQUEST FOR INFORMATION PCM3 #______(For PCM3 Use Only)

			RFI No.
TO: PCM3,		***************************************	1 Bid Pkg 9 RFI No.
	@pcm3.com gopian Contractor, Inc.	DWG, REF.:	
Fax No: 714-54	2-6925		
	D Football Field		
	_	Snec. Ref:	01 01 00-05
Bld Pack:	1 Tade not BP No.		6/16/2015
	Clarification / Information Req	uired:	
Regarding spec section 0	1 01 00-05 item c. Please prov	ide the value of Kya's prod	ucts and sevices that
Contractor will be safe ke	eping so that Contractor may	determine the risk.	
Drawings attached -			
Proposed Solution:			
•			
			,
Question By: P. H. Ha	gopian Contractor, Inc.	Date:	6/16/2015
n 1-mil	lion dollers (\$1,000	) 000 00)	
Response: 1-1111		5,000.00)	* • •
**			
			*
	Digitally signed by	Rrett Houser	
Response By: Bre	DN: co=Brett House	er.n=GBA, LLP, Date:	
Reviewed By: HO	USer Date: 2015.06.17		~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~

PCM3 #______(For PCM3 Use Only)

		<u></u>	RFI No.
		į	1 - 10 Bid Pka RFI No.
TO: PCM3, Inc. ckober@pcm3.c	Ref No.:		Bid Pkg. RFf No.
FROM: P.H. Hagopian	Contractor, Inc.	DWG. REF.:	
Fax No: 714-543-5825			
Site CCCD Foo	tball Field		
		Spec. Ref:	
Bid Pack: 1	N40.		6/16/2015
Description of Problem / Clarificat	tion / Information Required:		
The construction schedule is extr	emely aggressive. Will the Dis	trict make its ins	pectors available for
overtime and weekend work at no	extra cost? Or if there is an e	xtra cost, how m	uch will it be?
Drawings attached -			
Proposed Solution:			
Ownelles Dev D. H. Henryles	Ocutuation Inc	Data	CHCIONAT
Question By: P. H. Hagopian	Contractor, Inc.	Date:	6/16/2015
Response: Yes, the in	spector will be ava	ilable for o	vertime and
weekend w	ork at no extra cos	st to the co	ntractor.
Response By: Brett	Digitally signed by Brett Hou DN: cn=Brett Houser, o=G8A	LLD	
	email=bhouser@gbarchitect	s.net,	
Reviewed By: HOUSE	C=US Date: 2015.06.17 11:06:49 -07	Date:	

### REQUEST FOR INFORMATION

PCM3 #_____ (For PCM3 Use Only)

			1	RFI No.
	PCM3, Inc. Ref N ckober@pcm3.com	o.:		1 - 11 Bid Pkg. RFt No.
	P.H. Hagopian Contra	ictor, Inc.	DWG. REF.:	
Fax No:	714-543-5825			
Site	CCCD Football	Field		
			Spec. Ref:	
Bid Pack:	1 Trade not BP No.			6/16/2015
	blem / Clarification / Inheritation / Inheritation			
Drawings attached	-			
Proposed Solution	:			
Question By:	P. H. Hagoplan Contra	actor, Inc.	Date:	6/16/2015
Response:				
	See attached revised	Certificate of Insur	ance Spec Section 0	0-43-50.
		***************************************		
				ल कर
Response By:	Brett	Digitally signed by Brett Ho DN: cn=Brett Houser, o=GB	user Date:_	
Reviewed By:		ou, —email=bhouser@gbarchiteo	Deter	
	Houser	c=US Date: 2015.06.17 15:01:58 =	07'00'	

## REQUEST FOR INFORMATION

PCM3 #_____ (For PCM3 Use Only)

		RFI No.
TO: PCM3, Inc. Ref No.:		1 - 12 Bid Pkg RFI No.
ckober@pcm3.com	DWO 255	
FROM: P.H. Hagopian Contractor, Inc.	DWG. REF.:	
Fax No: 714-543-5825		
Site CCCD Football Field		
Bid Pack: 1 Trade not BP No.	Date: _	6/16/2015
Description of Problem / Clarification / Information		
is there a soils report and will it be made available?	<b>)</b> 	
Drawings attached -		
Proposed Solution:		
•		
Question By: P. H. Hagopian Contractor, Inc.	Date:	6/16/2015
Response: Yes, there is a soils re	nort and it is bein	a made
Response: Yes, there is a soils re available. Please see	•	g made
available. I lease see	Addendam No. 1	nema
From the following of the section of		
	igned by Brett Houser ett Houser, o=GBA,	
	Date;	
Reviewed By: et, c=US	Date:	

## REQUEST FOR INFORMATION

PCM3 #_____ (For PCM3 Use Only)

		RFI No.
TO: PCM3, Inc. Ref No	d d	1 - 13 Bid Pkg. RFI No.
ckober@pcm3.com	And the man	her.
FROM: P.H. Hagopian Contrac	tor, inc. DWG.	REF.;
Fax No: 714-543-5825		
Site <u>CCCD Football F</u>	<u>Field</u>	
	Spec	c. Ref:
Bid Pack: 1 Trade not BP No.		Date: 6/16/2015
<u>Trade</u> not BP No.		
Description of Problem / Clarification / Inf	ormation Required:	
Are any organics allowed in the field after	•	nuch?
on or Serios anomen in the nein sites	Tomovar or grass t it so, now f	muoli I
	¥ \$1577 d.A. \$1.4 \$1.61.6 d.A. d.A. d.A. d.A. d.A. b.A. b.A. b.A.	
		*!*!*!*!
Drawings attached -	<b>.</b>	
	***	
Proposed Solution:		
Question By: P. H. Hagopian Contrac	etor, Inc.	Date: 6/16/2015
Response: No organics will	be allowed.	
nesponse J. garnoo min		
<del></del>		ereceer
***************************************		
Response By: Brett	Digitally signed by Brett HouserDN:cn=Brett Houser, o=GBA, LLP,	Date:
	ou,	
Reviewed By: Houser	c=US	Date:
1104361	Date: 2015.06.17 11:11:25-07'00'	

## COMPTON COMMUNITY COLLEGE DISTRICT REQUEST FOR CLARIFICATION

PCM3 #_____(For PCM3 Use Only)
(ALL LINE ITEMS MUST BE COMPLETED PRIOR TO SUBMITTAL)

			RFC No.
TO: PCM3 ckober@pcm3,	Ref No.: BP #01		<u>01</u> 14
<del>-</del> '	com ction ohnocc@comcast.net	DWG. REF.: None	Bid Pkg. RFC No.
Fax No: 619-278-8761			
Site: CCCD Foo	tball Field		
		Spec. Ref:	00 43 50
Bid Pack: Football Field Name not BP No.			6/16/2015
Description of Problem / Clarifica	ition / Information Required:		
Please clarify what levels of insu	rance per category must be prov	rided by the contractor	and if these same levels
also apply to any subcontractors			
Drawings attached -	All Brid Allah All		
Proposed Solution Fill In required	insurance levels on the sample	certificate of insurance	<u> </u>
			100° No. 10 Personal Control of the
0			
Question By: Or	no Construction	Date:	6/16/2015
Response:		***	
See attached re	evised Certificate of Insurance S	pec Section 00-43-50.	
		<del></del>	
		·	
Response By:		Date:	·
Reviewed By:		Date:	

#### SECTION 11 68 33 - FOOTBALL FIELD EQUIPMENT

#### PART 1 - GENERAL

#### 1.1 SUMMARY

- A. Section Includes
  - 1. Equipment as scheduled
  - 2. Installation of required concrete footings

#### 1.2 SUBMITTALS

- A. Shop drawings, certified and stamped by manufacturer's engineer, showing plan layout of equipment, footing, mounting bolts dimensions, anchorages, and related installation detail for each type of equipment specified.
- B. Product data on operating equipment, characteristics and limitations.
- C. Product data.
- D. Three samples of materials and finishes.
- E. Manufacturer's installation instructions.
- F. Operation and maintenance data. Including data for maintaining operating equipment, type and frequency of lubrication, general instructions for maintaining finishes and prevention of deterioration.

#### 1.3 QUALITY ASSURANCE

A. Manufacturer: company with minimum 5-years experience manufacturing athletic equipment for high school project similar in scale and complexity to those required for this project.

#### 1,4 WARRANTY

A. Provide a 2-Year Warranty against defect in materials and installation commencing on Date of Certified Completion on equipment. Upon written notice form Owner they shall promptly, without cost, and with least practicable inconvenience to Owner correct such defects.

#### PART 2 - PRODUCTS

#### 2.1 MANUFACTURERS

- A. Acceptable Manufacturers. Products of following manufacturers form basis for design and quality intended.
  - Porter Athletic Equipment Company, Chatsworth, CA
  - Draper, Inc., Spiceland, IN
  - 3. AALCO, St. Louis, MO

- 4. Jaypro Sports Inc., Waterford, CT
- 5. PW Athletic Equipment, Prescott, AZ
- 6. Aluminum Athletic Equipment (AAE), West Conshohockern, PA
- 7. Spalding Equipment/BPI/American Athletic, Inc., Jefferson, IA
- 8. Sportsfield Specialties Inc., Delhi, NY
- 9. ACO Polymer Products, Inc.
- 10. Or equal, approved in accordance with Division 01, General Requirements, for substitutions.

#### 2.2 MATERIALS

- A. Concrete for Footings: Minimum 4500 psi compressive strength at 28 days and maximum 4-inch slump at placement.
- B. Reinforcing Steel: Provide cage reinforcement of No. 5 deformed bars in accordance with ASTM A 615, Grade 60, unless otherwise indicated.
- C. Athletic Equipment
  - 1. See Schedule of Athletic Equipment in Section 3.4 below.

#### PART 3 - EXECUTION

#### 3.1 INSPECTION

- A. Verify that structural supports, anchor bolts and backing are ready to receive work.
- B. Verify that proper power supply is available.
- C. Beginning installation means acceptance of existing conditions and preparatory work of others.

#### 3.2 INSTALLATION

- A. Install system and components in accordance with manufacturer's instructions.
- B. Install internal electrical wiring, conduits, junction boxes, transformers, circuit breakers and auxiliary components required.
- C. Support and anchor equipment and component assemblies per manufacturer's instructions.
- D. Install concrete footings according to manufacturer's details.

#### 3.3 TEST AND ADJUST

- A. Test and adjust systems for proper function.
- 3.4 SCHEDULE OF ATHLETIC EQUIPMENT

#### A. Communications Box

- Base: Combox 3500 as manufactured by Sportsfield Specialties, Inc., Delhi, NY. P.O. Box 231, 41155 State Highway 10, Delhi, NY, 13753. (888) 875-3343.
  - a. Box: 3/16" (0.1875") Aluminum Construction, Welded Frame with Open Bottom Having the Following Attributes:
    - 1) 30"L x 18"W x 14"H (Full Size) Custom Sizes Available Upon Request
    - 2) 1/8" (0.125") Aluminum Adjustable Main Cover Support Ledge
    - 3) 3/16" (0.1875") Aluminum Removable Divider Panel (Full Size Only)
    - 4) Integrated Synthetic Infill Turf Attachment Ledge and ComBox® +Patented Infill Retainer System with Flexible Gasket Seals (Synthetic Infill Turf Installation Applications Only)
    - 5) 1" PVC Drain Stub for Positive Drainage Connection.
  - b. Main Cover and Hand Hole(s): 1/8" (0.125") Aluminum Construction with the Following Attributes:
    - 1) ComBox® + Patented Infill Retainer System with Flexible
    - 2) Gasket Seals (Synthetic Infill Turf Installation Applications Only)
    - 3) Pad Lockable Main Cover and Turn Lockable Hand Hole(s)
    - 4) Wire Feed Cutouts Between Main Cover and Hand Hole(s)
    - Designed to Allow Synthetic Turf or Synthetic Track Material to be Adhered Directly to the Aluminum Surface with Synthetic Adhesive and/or Mechanical Fasteners Determined by Others
    - 6) Main Cover and Hand Hole(s) Style Synthetic Turf
  - c. Included Accessories:
    - 1) Stainless Steel Leveling Bolts
    - 2) Stainless Steel Assembly Hardware
    - 3) Factory Provided 3/8" Perforated Drainage Holes in Main Cover and Hand Hole(s) (Synthetic Infill Turf and Natural Grass Installation Applications Only)
    - 4) Model Specific Installation Instructions

END OF SECTION



## COMPTON COMMUNITY COLLEGE DISTRICT 1111 E. Artesia Blvd

Compton, California 90221 (310) 900-1600

Bid Pack #01

**Project Number: CCCD-026** 

#### **CERTIFICATE OF INSURANCE**

The undersigned, (the " <b>Insurance</b> <b>Company</b> "), hereby certifies to Compton Community College District (the "District") as follows:				
Company	to	of insurance (" <b>Policies</b> ") have (the "I of the execution of this Certificate	nsured"), and the	
Policy <u>Number</u>	Expiration <u>Date</u>	Type of Coverage	Amount of Coverage: Each Occurrence	Amount of Coverage: Aggregate
	,	A. GENERAL LIABILITY		
		Bodily Injury Property Damage Combined	\$ \$ \$ 1,000,000	\$ \$ \$ 2,000,000
	E	B. AUTOMOBILE LIABILITY		
		Bodily Injury (Each Person) Bodily Injury (All Persons) Combined	\$ \$ \$ 1,000,000	\$ \$ \$ 1,000,000
	(	C. EXCESS LIABILITY Combined	\$ 5,000,000	\$ 5,000,000

The following types of coverage are included in said policies (indicate by "X" in space):

A. GENERAL LIABILITY

Α.	GENERAL LIABILITY		
	Commercial General	YES	NO
	Comprehensive General	YES	NO
	Premises-Operations	YES	NO
	Explosion and Collapse Hazard	YES	NO
	Underground Hazard	YES	NO
	Products/Completed Operations	YES	NO
	Contractual Insurance	YES	NO
	Broad Form Property Damage		NO
	Including Completed Operations	YES	
	Independent Contractors	YES	NO
	Personal Injury	YES	NO
В.	AUTOMOBILE LIABILITY		
	Any Auto	YES	NO
C.	EXCESS LIABILITY		
	Umbrella Form	YES	NO
D.	EXCESS AUTOMOBILE LIABILITY		
	Umbrella Form	YES	NO
	Other Than Umbrella Form (Attach Explanation)	YES	NO
The	District is named as an additional insured	l on all such policies,	except as follows: (if

This Certificate of Insurance is not an insurance policy and does not amend, extend, or alter the coverage afforded by the Policies listed herein. Notwithstanding any requirement, term, or condition of any contract or other document with respect to which this Certificate of Insurance may be issued or may pertain, the insurance afforded by the Policies described herein is subject to all the terms, exclusions, and condition of

no exceptions, indicate "no exceptions"):

such Policies.

The Insurance Company will give at least thirty (30) days written notice by certified mail to the District and its architect or other designated consultant prior to any material change or cancellation of said Policies.

The Insurance Company is admitted and licensed to do business in California, has an agent for service of process in California, and has an "A" policyholder's rating and a financial size rating of at least Class VIII in accordance with the most current Best's Key Rating Guide, Property-Casualty.

Certificates of Insurance shall include all specific insurance coverage's set forth herein, proper Project description, designation of the District as the Certificate Holder, a statement that the insurance provided is primary to any insurance obtained by the District and minimum of 30 days' cancellation notice. Bidder shall also provide required additional insured endorsement(s) designating all parties required in the General Conditions. The additional insured endorsement shall be an ISO CG 20 10 (04/13), or an ISO CG 20 38 (04/13), or their equivalent as determined by the District in its sole discretion.

Insurance Company
Street Address
City and State
By: (Signature of Company Representative)
Printed Name:
Title:

No substitution or revision to the above certificate form will be accepted. If the insurance called for is provided by more than one insurance company, a separate certificate in the exact above form shall be provided for each insurance company.



GeoTek, Inc.
710 E. Parkridge Avenue, Suite 105, Corona, California 92879-1097
(951) 710-1160 Office (951) 710-1167 Fax www.geotekusa.com

June 10, 2015 Project No. 1337-CR

#### **Compton Community College District**

IIII East Artesia Boulevard Compton, California 90221-5393

Attention:

Ms. Linda Owens

Subject:

Alternative Site Preparation Recommendations

Proposed Football Field Redevelopment

IIII East Artesia Boulevard

City of Compton, Los Angeles County, California

Reference:

Limited Geotechnical and Pavement Evaluation, Proposed Football Field

Redevelopment, IIII East Artesia Boulevard, City of Compton, Los Angeles

County, California; GeoTek, Inc., June 8, 2015

Dear Ms. Owens:

The referenced report presents earthwork recommendations for the proposed football field redevelopment project on the campus of Compton Community College in the city of Compton. The existing grass football field will be replaced with a synthetic turf field. The new field will be underlain by three (3) inches of asphaltic concrete pavement over four (4) inches of aggregate base. To assist in the preparation of the referenced report, six hand-auger borings were excavated within the footprint of the football field. Undocumented fill consisting of medium stiff sandy silts was encountered in all the explorations to a depth of approximately 2.5 feet. The earthwork recommendations presented in the report included removal and recompaction of all undocumented fill. Since removal of all the fill is considered to be cost-prohibitive, alternative recommendations are now being presented.

An alternative to overexcavation and recompaction of the undocumented fill would be to remove the near-surface soils below the football field to a depth coincident with the top of the proposed subgrade below the bottom of the aggregate base.

The exposed soils should be observed by a representative of this firm prior to processing. Any residual vegetation should be removed and legally disposed of off-site. The exposed soils

should be scarified to a minimum depth of 12 inches, moisture conditioned to at least two percent over optimum, and densified to at least 90 percent relative compaction (ASTM D 1557). The underlying natural soils consisted of medium stiff sandy silts. The material encountered at a depth of two (2) feet in the southwest portion of the football field was in a wet condition. Wet soils should be removed and replaced with material that has a moisture content that is amenable to proper compaction.

This alternate method will leave some of the undocumented fill in place. Since preparation of the referenced report, we have been informed that there are existing storm drains, sanitary sewer, electrical and irrigation lines below the football field. The irrigation lines will be removed, and only the depth of the storm drain is known. Existing trench backfill will be associated with each of these utilities. Since the undocumented fill and utility trench backfill will not be removed, the property owner is accepting responsibility of the possibility that additional maintenance of the football field may be required during its design life.

In order to assist in minimizing future distress to the pavement section below the football field, consideration has been given to the implementation of geogrid. The geogrid should consist of Tensar BX 1200 or the equivalent. It should be placed on the subgrade soil, and the aggregate base placed and compacted on the geogrid. The aggregate base should be compacted to a minimum relative compaction of 95 percent (ASTM D1557).

The opportunity to be of service is sincerely appreciated. If you should have any questions,

No. 1892

please do not hesitate to contact our office.

Respectfully submitted,

GeoTek, Inc.

Distribution:

Edward H. LaMont CEG 1892, Exp. 07/31/16 Principal Geologist

(1) Addressee via email

Glenn S. Fraser

GE 2381, Exp. 9/30/15

Senior Engineer



# FOR PROPOSED FOOTBALL FIELD REDEVELOPMENT I I I EAST ARTESIA BOULEVARD COMPTON, LOS ANGELES COUNTY, CALIFORNIA

#### PREPARED FOR

COMPTON COMMUNITY COLLEGE DISTRICT IIII EAST ARTESIA BOULEVARD COMPTON, CALIFORNIA 90221-5393

PREPARED BY

GEOTEK, INC.
710 EAST PARKRIDGE AVENUE, SUITE 105
CORONA, CALIFORNIA 92879

PROJECT No. 1337-CR

JUNE 8, 2015





June 8, 2015 Project No. 1337-CR

#### **Compton Community College District**

IIII East Artesia Boulevard Compton, California 90221-5393

Attention: Ms. Linda Owens

Subject: Limited Geotechnical and Pavement Evaluation

Proposed Football Field Redevelopment

IIII East Artesia Boulevard

City of Compton, Los Angeles County, California

References: See page 10

#### Dear Ms. Owens:

In accordance with your request, GeoTek, Inc. (GeoTek) is providing a limited geotechnical and pavement evaluation for the proposed football field redevelopment. Project plans were not available at the time this report was prepared. Our current report includes the results of test borings excavated on the football field, asphalt coring results for the surrounding running track, and earthwork and pavement design recommendations.

#### SITE DESCRIPTION

The approximately 1.9-acre site is located on the campus of Compton Community College, situated on the north side of East Artesia Boulevard between Santa Fe Avenue and Long Beach Boulevard in the city of Compton, Los Angeles County, California. The location of the site is shown on Figure 1. The portion of the campus currently being evaluated has an existing grass football field with a goal post at each end, surrounded by an oval rubberized-surface running track and associated improvements. The property is rectangular in shape and is generally flat in topography.

#### PROPOSED DEVELOPMENT

We understand that anticipated site development will include replacing the existing grass football field with a synthetic turf field. The new synthetic turf field is likely to be supported by infill material, a polymeric panel, and a permeable geotextile fabric overlying a section of asphaltic concrete pavement over aggregate base. New goal posts are not included in the scope of this report. Minimal earthwork will be required for site development. It is our understanding that the Compton Community College District will not be making improvements to the running track at this time.

#### FIELD EXPLORATION

Our geotechnical field exploration was conducted on May 27, 2015. A field engineer from GeoTek logged seven exploratory borings excavated with hand-auger equipment. The borings were situated at various locations on the football field and were excavated to depths ranging from 2.5 feet to 3.5 feet below existing grade. The limited pavement evaluation consisted of advancing four core holes with a diamond-tipped core barrel through the existing pavement and measurement of the pavement sections (asphaltic concrete and aggregate base) in the oval rubberized-surface running track. A roto-hammer was used to loosen the underlying aggregate base and allow removal to the extent that the base thickness could be determined and the subgrade materials were exposed. The coring was performed by the Penhall Company, and GeoTek's representatives performed the roto-hammering and hand excavating. The thickness of the asphaltic concrete and base sections were measured at each core location. The core holes were generally located at or near the crown of the running track. measurements were obtained, the base materials were replaced in the excavation, tamped, and the remaining void filled with cold patch asphalt. The thickness of aggregate base was measured at four locations to the nearest 1/4-inch in each core hole and averaged (see "Limited Pavement Evaluation" section of this report).

The boring and core locations are presented on Figure 2. Logs of the exploratory borings are included in Appendix A. GeoTek obtained relatively undisturbed and bulk soil samples encountered in the test borings.

#### LABORATORY TESTING

Laboratory testing was performed on selected samples obtained during our field exploration. Included in our laboratory testing were moisture-density determinations on all undisturbed samples, and an expansion index test was performed on a bulk soil sample. A sample of



anticipated subgrade soil was tested for R-value determination for pavement design purposes, and soluble sulfate content testing was also conducted. The moisture-density data are presented on the exploration logs, presented in Appendix A. The R-value, expansion index, and soluble sulfate test data are presented in Appendix B.

#### **SOIL CONDITIONS**

Undocumented fill consisting of medium stiff sandy silts was encountered in all the explorations to a depth of 2.5 feet. The underlying natural soils also consisted of medium stiff sandy silts. In general the soils were in a slightly moist condition, however, the material encountered at a depth of 2.0 feet in Boring HA-6 was in a wet condition. The boring logs are presented in Appendix A. The near-surface soils generally have a "low" expansion potential.

#### CONCLUSIONS AND RECOMMENDATIONS

The anticipated site development appears feasible from a geotechnical viewpoint provided that the following recommendations, and those provided by this firm at a later date, are properly incorporated into the design and construction phases of development. Site development and grading plans should be reviewed by GeoTek when they become available.

#### **EARTHWORK CONSIDERATIONS**

#### General

Earthwork and grading should be performed in accordance with the applicable grading ordinances of the County of Los Angeles and City of Compton, the 2013 California Building Code (CBC), and recommendations contained in this report.

#### Site Preparation

Existing improvements should be demolished and the debris legally disposed of off-site. Deleterious materials and vegetation should also be removed. Any existing underground improvements, utilities and associated trench backfill should also be removed or be further evaluated as part of site development operations.

#### Remedial Grading

All undocumented fill should be removed below the footprint of the football field. The fill may be stockpiled on-site for future use. Based on the results of our test borings, the fill extended to a depth of approximately 2.5 feet below existing grade. Deeper areas of fill may be



Project No. 1337-CR June 8, 2015 Page 5

encountered in areas that were not explored. In addition to removal of the fill, the natural soils below the bottom of the proposed aggregate base that will be placed below the synthetic turf should be overexcavated to a depth of two (2) feet below existing grade or two (2) feet below proposed finished grade, whichever is greater. Finished grade is defined as the elevation of the top of the subgrade below the aggregate base.

A representative of this firm should observe the bottom of all excavations prior to processing.

The lateral extent of removals beyond the outside edge of the synthetic turf should be at least two (2) feet or equal to the depth of overexcavation, whichever is greater.

Upon approval, the bottom of all removals and all areas to receive fill should be scarified to a minimum depth of one (1) foot, brought to at least 2% above the optimum moisture content and compacted to at least 90 percent relative compaction (ASTM D1557).

At the time of our subsurface exploration, the soils in the vicinity of Boring HA-6 exhibited a relatively high moisture content. If the soils are at a similar moisture content at the time of remedial grading the subexcavated surfaces may become unstable and pumping may occur. Stabilization may be required. Stabilization can often be accomplished by placing geogrid, such as Tensar BX1200, on the unstable subgrade, followed by at least 18 inches of gravel, such as Caltrans Class II aggregate base. If sufficient stabilization has not been attained with one layer of geogrid and 18 inches of aggregate base, an additional layer of geogrid should be placed, followed by 12 inches of aggregate base.

We recommend that an alternate bid for subsoil stabilization be included in the Construction Bid Documents.

#### **Engineered Fill**

The on-site soils are generally considered suitable for reuse as engineered fill provided they are free from vegetation, debris and other deleterious material. Engineered fill should be placed in six (6) inch to eight (8) inch loose lifts, moisture conditioned to at least 2% above the optimum moisture content and compacted to a minimum relative compaction of 90 percent (ASTM D1557).

Aggregate base should be compacted to a minimum relative compaction of 95 percent (ASTM D1557).



#### **Chemical Test Results**

Chemical testing consisting of a soluble sulfate analysis was conducted on a representative soil sample obtained during the field exploration. The results indicate that the water soluble sulfate is less than 0.1 percent by weight, which is considered "not applicable" (negligible) as per Table 4.2.1 of ACI 318.

It is recommended that soluble sulfate testing be performed during earthwork operations when the mass grading nears completion and finished grade levels are almost achieved. Additional recommendations will be presented at that time.

#### Drainage

Positive site drainage should be maintained at all times. Water should be directed away from the synthetic turf field and not allowed to pond or seep into the ground adjacent to it. Drainage should be directed toward approved areas and not be blocked by other improvements.

It is the owner's responsibility to maintain and clean drainage devices on their property. In order to be effective, maintenance should be conducted on a regular and routine schedule and necessary corrections made prior to each rainy season.

#### PAVEMENT DESIGN RECOMMENDATIONS

#### General

These recommendations are based on sampling and R-Value testing of the on-site football field subgrade soils and an anticipated total vehicle load of 8,000 pounds. The calculation to determine the thickness of an asphalt concrete pavement section is partially based on the implementation of a Traffic Index (TI). A TI of 4.0 and an R-Value of 38 was used for preliminary design purposes (see below).



#### Sampling and Testing

During our recent field investigation GeoTek obtained a near surface soil sample from within the existing football field for R-Value testing. The testing (by others) indicated an R-Value of 38.

#### **Asphaltic Concrete Pavement Section**

The table below provides the location, associated TI and the recommended minimum pavement section for the subject project.

Location	Assigned Traffic Index (TI)	Design R-Value	Recommended Minimum Section - Asphaltic Concrete/Aggregate Base (inches)
Synthetic Turf Field	4.0	38	3.0/4.0

The pavement section is subject to review and approval by the City of Compton. Performance of the pavement section will ultimately be based largely on construction methods, surface loading and subgrade performance.

#### **Pavement Construction**

All pavement installation, including preparation and compaction of subgrade and base material and placement and rolling of asphaltic concrete should be done in accordance with the City of Compton specifications, and under the observation and testing of GeoTek and a City inspector where required.

The aggregate base should consist of crushed rock with an R-Value and gradation in accordance with Crushed Aggregate Base (Section 200-2 of the "Greenbook"). Minimum compaction requirements should be 90 percent for subgrade and 95 percent for aggregate base, as per ASTM D1557. Jurisdictional minimum compaction requirements in excess of the aforementioned minimums may govern.



#### LIMITED PAVEMENT EVALUATION, EXISTING RUNNING TRACK

The exact age of the existing running track pavement is unknown. Each core had a layer of 1/4-to 1/2-inch of rubberized-surface material over the asphaltic concrete. The thickness of the asphalt concrete and underlying base are summarized in the following table:

Core	Approximate Average Thickness of Existing Asphaltic Concrete (inches)	Approximate Average Thickness of Existing Aggregate Base (inches)
C-I	3.25	4.0
C-2	3.5	3.0
C-3	3.5	5.0
C-4	3.5	5.0

#### INTENT

It is the intent of this report to aid in the design and construction of the proposed development. The professional opinions and geotechnical advice contained in this report are not intended to imply total performance of the project or guarantee that unusual or variable conditions will not be discovered during or after construction.

The scope of our evaluation is limited to the boundaries of the existing football field. This review does not and should in no way be construed to encompass any areas beyond the specific site of the proposed construction as indicated to us by the client. Further, no evaluation of any existing site improvements is included. The scope is based on our understanding of the project and the client's needs, our fee estimate and geotechnical engineering standards normally used on similar projects in this region.

#### **LIMITATIONS**

The materials observed on the project site appear to be representative of the area; however, soils vary in character between excavations exposed during site construction. Site conditions may vary due to seasonal changes or other factors. GeoTek assumes no responsibility or liability for work, testing or recommendations performed or provided by others.



Observations during construction are important to allow for any change in recommendations that are found to be warranted. These opinions have been derived in accordance with current standards of practice and no warranty is expressed or implied. Standards of practice are subject to change with time. The opportunity to be of service is sincerely appreciated. If you should have any questions, please do not hesitate to call our office.

No. 1892

Respectfully submitted,

GeoTek, Inc.

Glenn S. Fraser

GE 2381, Exp. 9/30/15

Senior Engineer

Edward H. LaMont CEG 1892, Exp. 07/31/16

Principal Geologist

Enclosures: Figure I – Site Location Map

Figure 2 – Exploration Location Map

Appendix A - Boring Logs

Appendix B - Laboratory Test Results

Distribution: (1) Addressee via email


#### **REFERENCES**

American Society of Civil Engineers (ASCE), 2013, "Minimum Design Loads for Buildings and Other Structures," ASCE/SEI 7-10, Third Printing, Errata Incorporated through March 15.

California Building Standards Commission, 2013, "California Building Code," 3 Volumes.

GeoTek, Inc., In-house proprietary information.





#### **Compton Community College District**

Football Field Redevelopment
IIII East Artesia Boulevard
City of Compton,
Los Angeles County, California


GeoTek Project No. 1337-CR



Figure 1

Site Location Map





Compton Community College District
Football Field Redevelopment
IIII East Artesia Boulevard
City of Compton,
Los Angeles County, California

GeoTek Project No. 1337-CR



Exploration Location Map



## **APPENDIX A**

**BORING LOGS** 



CLIENT:	Compton Community College District	LOGGED BY:	RН
PROJECT NAME:	Football Field Redevelopment	DRILL METHOD:	Hand Auger
PROJECT NO.:	1337-CR	DATE:	5/27/2015
LOCATION:	See Exploration Location Map	_	

				See Exploration Cocation Frap			
		MPLES	_			Labora	tory Testing
Depth (ft)	Sample Type	Sample Number	USCS Symbol	BORING NO.: HA-I	Water Content (%)	Dry Density (pcf)	Others
	۷,			MATERIAL DESCRIPTION AND COMMENTS	3		
		LB-I R-I	ML	Artificial Fill 0-2.5': Light brown sandy silt, slightly moist, medium stiff	6.0	100.3	EI, SR
				BORING TERMINATED AT 2.5 FEET			
10				No groundwater encountered Boring backfilled with on-site soils			
LEGEND		ple typ		RingLarge Bulk  AL = Atterberg Limits EI = Expansion Index SA = Sieve An	JusticeV		e R-Value Test
H.				SR = Sulfate/Resistivity Test SH = Shear Test HC = Consolid			Maximum Density

CLIENT:	Compton Community College District	LOGGED BY:	RH
PROJECT NAME:	Football Field Redevelopment	DRILL METHOD:	Hand Auger
PROJECT NO.:	1337-CR	DATE:	5/27/2015
LOCATION:	See Exploration Location Map	_	

LOC	X I I O	N:		See Exploration Location Map			
	SA	MPLES				Labora	atory Testing
Depth (ft)	Sample Type	Sample Number	USCS Symbol	BORING NO.: HA-2	Water Content	Dry Density (pcf)	Others
	s,	Sar		MATERIAL DESCRIPTION AND COMMENTS	\$	Δ	
- -		R-I	ML	Artificial Fill 0-2.5': Brown sandy silt, slightly moist, medium stiff	11.6	90.1	
-		R-2			10.8	94.4	
-		11.2		BORING TERMINATED AT 2.5 FEET	7.0.0	' '' '	
5				No groundwater encountered Boring backfilled with on-site soils			
9	Sam	ple typ	<u>e</u> :	RingLarge Bulk	<u> </u>	Water Tab	le
LEGEND		testing	1	AL = Atterberg Limits EI = Expansion Index SA = Side	eve Analysis Consolidation	RV =	R-Value Test = Maximum Density

CLIENT:	Compton Community College District	LOGGED BY:	RH
PROJECT NAME:	Football Field Redevelopment	DRILL METHOD:	Hand Auger
PROJECT NO.:	1337-CR	DATE:	5/27/2015
LOCATION:	See Exploration Location Map	•	

	LOCATION: See Exploration Location Plap										
	SAMPLES							Laboratory Testing			
Depth (ft)	Sample Type	Sample Number	USCS Symbol		RING NO.: HA-3		Water Content (%)	Dry Density (pcf)	Others		
	S	San		MATERIAL DE	SCRIPTION AND COMMEN	NTS	ş	Δ			
-		R-I	ML	Artificial Fill 0-2.5': Brown sandy silt, slig	ghtly moist, medium stiff		12.4	99.4			
Ι.		R-2					7.6	83.3			
5				BORING T							
-		ļ									
LEGEND		ple typ		Ring	Large Bulk			Vater Tabl			
LEG	Lab	testing		AL = Atterberg Limits SR = Sulfate/Resistivity Test	EI = Expansion Index SH = Shear Test	SA = Sieve Analy HC= Consolidat			R-Value Test Maximum Density		

CLIENT:	Compton Community College District	LOGGED BY:	RH
PROJECT NAME:	Football Field Redevelopment	DRILL METHOD:	Hand Auger
PROJECT NO.:	1337-CR	DATE:	5/27/2015
LOCATION:	See Exploration Location Map	_	

LOC	CCATION: See Exploration Location Map							
	SA	MPLES				Labora	tory Testing	
Depth (ft)	Sample Type	Sample Number	USCS Symbol	BORING NO.: HA-4	Water Content (%)	Dry Density (pcf)	Others	
	Sar	Sam	-,	MATERIAL DESCRIPTION AND COMMENTS		۵	-	
	X	LB-I R-I	ML	Artificial Fill 0-2.5': Brown sandy silt, dry to slightly moist, medium stiff	4.9	93.4	RV	
		R-2			7.6	91.2		
•				Alluvium	1			
			ML	2.5': Brown sandy silt, moist, medium stiff (Original Ground)				
		_		BORING TERMINATED AT 3 FEET				
5.				No groundwater encountered Boring backfilled with on-site soils				
,								
10								
15								
LEGEND		ple typ		RingLarge Bulk		Vater Tabl		
TEG	Lab	testing	:	AL = Atterberg Limits EI = Expansion Index SA = Sieve And SR = Sulfate/Resistivity Test SH = Shear Test HC= Consolid			R-Value Test Maximum Density	

CLIENT:	Compton Community College District	LOGGED BY:	RH
PROJECT NAME:	Football Field Redevelopment	DRILL METHOD:	Hand Auger
PROJECT NO.:	1337-CR	DATE:	5/27/2015
LOCATION:	See Exploration Location Map	_	

LOC	OCATION: See Exploration Location Map								
	SA	MPLES			L	Labora	atory Testing		
Depth (ft)	Sample Type	Sample Number	USCS Symbol	BORING NO.: HA-5	Water Content (%)	Dry Density (pcf)	Others		
	r.S.	Sam		MATERIAL DESCRIPTION AND COMMENTS	≶	Δ			
		R-I	ML	Artificial Fill 0-2.5': Light brown sandy silt, dry, medium stiff	5.6	96.9			
	_	R-2			7.0	84.7			
		11-2		BORING TERMINATED AT 2.5 FEET	7.0	01.7			
10				No groundwater encountered Boring backfilled with on-site soils					
LEGEND		ple typ		RingLarge Bulk  AL = Atterberg Limits EI = Expansion Index SA = Sieve Ana	∑V Tysis		le R-Value Test		
٦				SR = Sulfate/Resistivity Test SH = Shear Test HC = Consolid		MD =	Maximum Density		

CLIENT:	Compton Community College District	LOGGED BY:	RH
PROJECT NAME:	Football Field Redevelopment	DRILL METHOD:	Hand Auger
PROJECT NO.:	1337-CR	DATE:	5/27/2015
LOCATION:	See Exploration Location Map	_	

LOC	OCATION: See Exploration Location Map								
	SA	MPLES			111200011			Labora	atory Testing
Depth (ft)	Sample Type	Sample Number	USCS Symbol		BORING NO.: HA-6		Water Content (%)	Dry Density (pcf)	Others
	Sa	Sam		MATERIA	L DESCRIPTION AND COM	IMENTS	, Š	۵	<del>-</del>
			ML	Artificial Fill 0-2.5': Brown sandy s	silt, moist, medium stiff				-
ĺ	_	R∗I					15.9	104.5	
		R-2		2': Becomes wetter			19.5	98.9	
	_			BORI	NG TERMINATED AT 2.5 FI	ET			
10				No groundwater enco Boring backfilled with	ountered				
-									
	Sam	ple typ	<u>e</u> :	Ring	Large Bulk	,	¥v	/ater Table	e
LEGEND	Lab	testing		AL = Atterberg Limits SR = Sulfate/Resistivity Test	El = Expansion Index SH = Shear Test	SA = Sieve Analy HC= Consolida			R-Value Test Maximum Density

CLIENT:	Compton Community College District	LOGGED BY:	RH
PROJECT NAME:	Football Field Redevelopment	DRILL METHOD:	Hand Auger
PROJECT NO.:	1337-CR	DATE:	5/27/2015
LOCATION			

LO	CATIC	ON:		See Exploration Location Map			
	S.	AMPLES			T	Labor	atory Testing
Depth (ft)	Sample Type	Sample Number	USCS Symbol	BORING NO.: HA-7	Water Content (%)	Dry Density (pcf)	Others
	Sa	Sam		MATERIAL DESCRIPTION AND COMMENTS	×	۵	Ĭ
			ML	Artificial Fill 0-2.5': Brown sandy silt, slightly moist, medium stiff			
	_			Alluvium			
		R-I	ML	2.5': Brown sandy silt, moist, medium stiff (Original Ground)  BORING TERMINATED AT 3.5 FEET	7.5	83.8	
10				No groundwater encountered Boring backfilled with on-site soils			
9	Sam	ple typ	<u>e</u> :	RingLarge Bulk	<u> </u>	ater Tabl	e
LEGEND		testing:		AL = Atterberg Limits EI = Expansion Index SA = Sieve Analy SR = Sulfate/Resistivity Test SH = Shear Test HC = Consolidat	sis	RV =	R-Value Test Maximum Density

## **APPENDIX B**

LABORATORY TEST RESULTS





# **EXPANSION INDEX TEST**

## (ASTM D4829)

Corona

Lab No

Tested/ Checked By:

Light brown f-m sandy silt

Sample Description:

Date Tested: Sample Source:

DI 5/31/2015 B-1 @ 0-2.5'

Compton Community College District
Project Number: 1337-CR
Project Location: 1111 E. Artesia Blvd., Compton, CA

Ring #: R-1 Ring Dia. : 4.01" Ring Ht.1"

## DENSITY DETERMINATION

4	A Weight of compacted sample & ring (gm)	738.8
Ω	B Weight of ring (gm)	366.2
ပ	C Net weight of sample (gm)	372.6
Ω	D Wet Density, lb / ft3 (C*0.3016)	112.4
ш	E Dry Density, lb / ft3 (D/1.F)	99.4

## SATURATION DETERMINATION

щ	Moisture Content, %	13.0
G	G Specific Gravity, assumed	2.70
I	H Unit Wt. of Water @ 20°C, (pcf)	62.3
	I % Saturation	50.8

		Initial	10 min/Dry		Final
	READING	0.3300	0.3300		0.3510
READINGS	TIME	4:16	4:26		4:11
22	DATE	5/31/2015	5/31/2015		6/1/2015

FINAL M	FINAL MOISTURE
sample & tare	% Moisture
772.1	21.9

## EXPANSION INDEX =

7

## Cal Land Engineering, Inc. dba Quartech Consultants

Geotechnical, Environmental, and Civil Engineering

GeoTek, Inc. 710 East Parkridge Avenue, Suite 105 Corona, California 92879

Client: Compton College

W.O.: 1337-CR

Project: 1111 E. Artesia Blvd, Compton

Date: June 4, 2015

QCI Project No.: 15-167-006b

Summarized by: KA

Sample ID	Sample Depth	Sulfate CT-417 (% By Weight)
B-1	0-3'	0.0160

PROFESSIONAL PAVEMENT ENGINEERING

A CALIFORNIA CORPORATION

May 28, 2015

Ms. Anna Scott GeoTek Inc. 710 East Parkridge Avenue, Suite 105 Corona, California 92879

Project No. 40271

Dear Ms. Scott:

Testing of the bulk soil sample delivered to our laboratory on 5/27/2015 has been completed.

Reference:

W.O. #1337-CR3 grade de la casa.

Project:

Compton College Football Field

Sample:

B-4 @ 0'-3', 5/27/2015

R-Value data sheets are attached for your use and file. Any untested portion of the sample will be retained for a period of 60 days prior to disposal. The opportunity to be of service is sincerely appreciated and should you have any questions, kindly call.

Respectfully Submitted,

Steven R. Marvin *RCE 30659* 

SRM:rse

## R - VALUE DATA SHEET

W.O. 1337-CR3

CALIBLE BEGGETTER	vn Sandy Silt			Compton BORING NUMBER: B-4 @ 0'-3'			
SAMPLE DESCRIPTION: Brov							
ltem			SPECIMEN				
	а		b	С			
Mold Number	16		17	18			
Water added, grams	84		104	93			
Initial Test Water, %	16.1		18.0	17.0			
Compact Gage Pressure,psi	110		80	95			
Exudation Pressure, psi	617		161	334			
Height Sample, Inches	2.50		2.61	2.54			
Gross Weight Mold, grams	2971		2984	2984			
Tare Weight Mold, grams	1957	7	1951	1967			
Sample Wet Weight, grams	1014	l	1033	1017			
Expansion, Inches x 10exp-4	70		38	50			
Stability 2,000 lbs (160psi)	25 /	49	27 / 58	26 / 53			
Turns Displacement	6.45		7.13	7.00			
R-Value Uncorrected	47		38	42			
R-Value Corrected	47		41	42			
Dry Density, pcf	105.9		101.6 103.7				
		DESIGN	CALCULATION	DATA			
Traffic Index Assume	d: 4.0		4.0	4.0			
G.E. by Stability	0.54		0.60	0.59			
G. E. by Expansion	2.33		1.27	1.67			
	38	Exar	nined & Checked:	5 /28/ 15			
Equilibrium R-Value	by		OPROFESSION .				
	XPANSION	ĺ					
A		1	BEN R. A	6 7 G.			
Gf = 1.25		1	Examined & Checked: 5 /28/ 15				
0.0% Retain	ed on the	1					
EMARKS: 3/4" Sieve.		1					
Mary professor Ad Administration for a page angular galled deviction and contract contract and c		Steven W. Marvini Rek		REENS 659			
he data above is based upon proces	sing and tooti	ing and testing samples as received from					

The data above is based upon processing and testing samples as received from the field. Test procedures in accordance with latest revisions to Department of Transportation, State of California, Materials & Research Test Method No. 301.

### R-VALUE GRAPHICAL PRESENTATION

	COMPACTOR PRESSURE, LBS.  COMPACTOR PRESSURE
800 700 600 500 400 300 200 100  90  80  70  60  50  40  1.0 2.0 3.0 4.0  COVER THICKNESS BY EXPANSION, FT.	4.0 3.0 2.0 2.0 3.0 3.0 3.0 3.0 3.0 3.0 3.0 3.0 3.0 3
RVALUE vs. EXUD. PR EXUD. T vs. EXPAN. T REMARKS	A CONTRACTOR OF THE PARTY OF TH
	(A=1.25